



Omschrijving	Locatie	BegIn-Eind/Cyclus	Aantal	Prijs/eh	Totaal	DH	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	Totaal
<b>14 BUITENRIOLERING</b>																	
						subtotaal	<b>328</b>	<b>518</b>	<b>328</b>	<b>328</b>	<b>518</b>	<b>328</b>	<b>328</b>	<b>518</b>	<b>328</b>	<b>328</b>	<b>3.847</b>
<b>14 10 Rioleringsleidingen</b>																	
01	Inspectie	2012 -	/ 3	1 po	157	190 B	.	190	.	.	190	.	.	190	.	.	570
03	Riolering ontstoppen	2000 -	/ 1	1 st	148	179 B	179	179	179	179	179	179	179	179	179	179	1.789
<b>14 20 Putten en kolken</b>																	
01	Putten/kolken schoonmaken	2000 -	/ 1	15 st	8	149 B	149	149	149	149	149	149	149	149	149	149	1.488
<b>15 BESTRATING</b>																	
						subtotaal	.	.	.	<b>2.977</b>	.	.	.	.	.	.	<b>2.977</b>
<b>15 20 Straatst.bestrating</b>																	
03	herstraten overig	2017 -	/ 15	150 m2	16	2.977 B	.	.	.	2.977	.	.	.	.	.	.	2.977
<b>16 BEPLANTING</b>																	
						subtotaal	<b>121</b>	<b>121</b>	<b>121</b>	<b>121</b>	<b>121</b>	<b>121</b>	<b>121</b>	<b>121</b>	<b>121</b>	<b>121</b>	<b>1.210</b>
<b>16 96 Groenvoorziening</b>																	
01	Planten	2004 -	/ 1	1 po	100	121 B	121	121	121	121	121	121	121	121	121	121	1.210
<b>17 TERREININVENTARIS</b>																	
						subtotaal	.	.	.	.	.	.	.	.	<b>138</b>	.	<b>138</b>
<b>17 95 Rijkwielvoorziening</b>																	
01	Rijkwielrekken gebreken herstellen	2022 -	/ 6	1 po	114	138 B	.	.	.	.	.	.	.	.	138	.	138
<b>21 BETONWERK</b>																	
						subtotaal	<b>1.815</b>	.	.	.	.	.	<b>133</b>	<b>631</b>	.	.	<b>2.579</b>
<b>21 30 Gepref. beton</b>																	
80	Betonlateien coaten	2003 -	/ 9	53 m1	10	631 B	.	.	.	.	.	.	.	631	.	.	631
<b>21 40 Bescherm. betonwerk</b>																	
01	2 comp.coating op betonvloer gebreken herst.	2002 -	/ 9	4 m2	28	133 B	.	.	.	.	.	.	133	.	.	.	133
<b>21 90 Overige betonwerk</b>																	
01	herstel schade bij doorbuiging	2014 -	/ 18	1 po	1.500	1.815 B	1.815	.	.	.	.	.	.	.	.	.	1.815
<b>22 METSELWERK</b>																	
						subtotaal	.	.	.	.	.	.	<b>1.851</b>	.	<b>3.136</b>	.	<b>4.988</b>
<b>22 11 Voegwerk</b>																	
51	Voegwerk vervangen	2000 -	/ 20	50 m2	31	1.851 B	.	.	.	.	.	.	1.851	.	.	.	1.851
<b>22 43 Dilatatievoegen</b>																	
02	Dilatatievoeg vervangen	2022 -	/ 18	54 m1	48	3.136 B	.	.	.	.	.	.	.	.	3.136	.	3.136
<b>30 KOZIJNEN+RAMEN+DEUREN</b>																	
						subtotaal	<b>183</b>	<b>183</b>	<b>183</b>	<b>183</b>	<b>183</b>	<b>183</b>	<b>183</b>	<b>183</b>	<b>183</b>	<b>183</b>	<b>1.833</b>
<b>30 15 Hang/sluitwerk</b>																	
01	Hang- & sluitwerk gebreken herstellen	2012 -	/ 1	1 po	152	183 B	183	183	183	183	183	183	183	183	183	183	1.833
<b>31 BUITENTIMMERWERK</b>																	
						subtotaal	.	.	.	.	<b>1.085</b>	.	.	.	.	.	<b>1.085</b>
<b>31 10 Gevelbekleding</b>																	
01	Gevelbekleding gebreken herstellen	2012 -	/ 6	74 m2	5	448 B	.	.	.	.	448	.	.	.	.	.	448
76	Gevelbekleding schoonmaken	2012 -	/ 6	55 m2	10	637 B	.	.	.	.	637	.	.	.	.	.	637
<b>32 TRAPPEN + HEKKEN</b>																	
						subtotaal	<b>1.742</b>	.	.	.	<b>148</b>	.	.	.	.	.	<b>1.890</b>
<b>32 10 Trappen</b>																	
01	Treden en kantstukken vastzetten (epoxy)	2014 -	/ 0	32 st	45	1.742 B	1.742	.	.	.	.	.	.	.	.	.	1.742
02	Verdiepingstrappen gebreken herstellen	1994 -	/ 6	2 st	61	148 B	.	.	.	.	148	.	.	.	.	.	148
<b>33 DAKBEDEKKING</b>																	
						subtotaal	<b>133</b>	<b>13.702</b>	<b>13.702</b>	<b>13.702</b>	<b>13.702</b>	<b>13.702</b>	<b>14.718</b>	<b>13.702</b>	<b>13.702</b>	<b>19.712</b>	<b>130.476</b>



Omschrijving	Locatie	Begin-Eind/Cyclus	Aantal	Prijs/eh	Totaal	DH	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	Totaal	
<b>33 10 Dakpannen</b>																		
05	Dakvlak schoonmaken	2000 - / 1	1 po	110	133	B	133	133	133	133	133	133	133	133	133	133	1.329	
<b>33 50 Bitumin. bedekking</b>																		
01	Bitumen dakbedekking vervangen	Liftpbouw	2002 - / 18	30 m2	28	1.016	B	.	.	.	.	.	1.016	.	.	.	1.016	
01	Bitumen dakbedekking vervangen	dak	2005 - / 18	160 m2	28	5.421	B	.	.	.	.	.	.	.	.	5.421	5.421	
03	Balkonvloeren afwerken gefaseerd	balkons	2015 - 2023 / 1	18 st	623	13.569	B	.	13.569	13.569	13.569	13.569	13.569	13.569	13.569	13.569	122.120	
<b>33 91 Dakdoorvoeren</b>																		
02	Ontluchtingsdoorvoeren vervangen		2023 - / 18	14 st	35	589	B	.	.	.	.	.	.	.	.	589	589	
<b>34 GOTEN EN HW AFVOEREN</b>							subtotaal	.	<b>8.189</b>	.	.	.	.	.	.	.	<b>8.189</b>	
<b>34 30 Hemelwaterafvoeren</b>																		
02	Hemelwaterafvoeren vervangen (inclusief beugels)		2015 - / 24	376 m1	18	8.189	B	.	8.189	.	.	.	.	.	.	.	8.189	
<b>42 VLOERAFWERKINGEN</b>							subtotaal	<b>6.279</b>	<b>6.279</b>	<b>8.170</b>	<b>6.279</b>	<b>16.773</b>	<b>10.669</b>	.	<b>1.892</b>	.	.	<b>56.340</b>
<b>42 30 Vloerbedekking</b>																		
01	Vloerbedekking vervangen (140 m2 / gang)	gangen	2012 - 2019 / 1	140 m2	37	6.279	B	6.279	6.279	6.279	6.279	6.279	6.279	.	.	.	37.671	
02	Vloerbedekking vervangen	bestuursruimten	2018 - / 12	234 m2	37	10.494	B	.	.	.	10.494	.	.	.	.	.	10.494	
02	Marmoleum vervangen		1999 - / 20	70 m2	52	4.391	B	.	.	.	.	4.391	.	.	.	.	4.391	
04	Inlooptapijt / kokosmat vervangen		2001 - / 5	20 M2	78	1.892	B	.	.	1.892	.	.	.	1.892	.	.	3.783	
<b>44 PLAFONDS EN WANDSYSTEEM</b>							subtotaal	<b>27.035</b>	.	.	.	<b>69</b>	.	.	.	.	<b>27.104</b>	
<b>44 10 Plafonds</b>																		
03	Plafonds gebreken herstellen		2000 - / 6	1 po	57	69	B	.	.	.	69	.	.	.	.	.	69	
07	Systeemplafondplaten vervangen (140 m2 / gang)		2014 - /	1000 m2	22	27.035	B	27.035	.	.	.	.	.	.	.	.	27.035	
<b>47 BUITENSCHILDERWERK</b>							subtotaal	.	.	<b>6.645</b>	<b>55.950</b>	<b>53.409</b>	.	.	<b>6.645</b>	<b>55.950</b>	<b>53.409</b>	<b>232.010</b>
<b>47 10 Buitenschilderwerk</b>																		
05	Buitenschilderwerk		2011 - / 5	5 po	1.098	6.645	B	.	.	6.645	.	.	.	6.645	.	.	13.291	
<b>47 99 Diversen</b>																		
10	Gevel Achter en rechts groot		2012 - / 5	1 po	39.640	47.964	B	.	.	.	47.964	.	.	.	47.964	.	95.929	
12	Gevel Voor en Links groot		2013 - / 5	1 po	39.640	47.964	B	.	.	.	47.964	.	.	.	.	47.964	95.929	
20	Gevel Achter in pandig		2017 - / 5	1 po	4.500	5.445	B	.	.	.	5.445	.	.	.	5.445	.	10.890	
21	Gevel Voor in pandig		2018 - / 5	1 po	4.500	5.445	B	.	.	.	5.445	.	.	.	.	5.445	10.890	
30	Dakopbouw		2012 - / 5	1 po	2.100	2.541	B	.	.	.	2.541	.	.	.	2.541	.	5.082	
<b>49 BEHANGWERK</b>							subtotaal	.	.	.	.	.	.	.	.	<b>1.109</b>	<b>1.109</b>	
<b>49 10 Behangwerk</b>																		
01	Behangwerk vervangen		2005 - / 18	122 m2	8	1.109	B	.	.	.	.	.	.	.	.	1.109	1.109	
<b>52 BINNENRIOLERING</b>							subtotaal	<b>128</b>	<b>128</b>	<b>128</b>	<b>128</b>	<b>128</b>	<b>128</b>	<b>128</b>	<b>128</b>	<b>128</b>	<b>128</b>	<b>1.276</b>
<b>52 10 Leidingen</b>																		
02	Rioleringsleidingen ontstoppen		2000 - / 1	1 st	105	128	B	128	128	128	128	128	128	128	128	128	1.276	
<b>53 WATERINSTALLATIE</b>							subtotaal	.	.	.	.	.	.	<b>502</b>	.	.	.	<b>502</b>
<b>53 40 Warmwatertoestel</b>																		
01	Close-up boiler vervangen (5 liter)		2005 - / 15	1 st	414	502	B	.	.	.	.	.	502	.	.	.	502	
<b>54 GASINSTALLATIE</b>							subtotaal	.	.	<b>119</b>	.	.	.	.	.	<b>119</b>	.	<b>239</b>





Omschrijving	Locatie	Begin-Eind/Cyclus	Aantal	Prijs/eh	Totaal	DH	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	Totaal	
10	Vervanging alarminstallatie	2004 - / 12	1 po	624	755	B	.	.	755	.	.	.	.	.	.	.	755	
<b>67 LIFTINSTALLATIE</b>							subtotaal	<b>14.520</b>	.	.	.	.	.	.	.	.	.	<b>14.520</b>
<b>67 10 Liften</b>																		
02	vervangen motor	2014 - / 0	1 po	12.000	14.520	B	14.520	.	.	.	.	.	.	.	.	.	14.520	
<b>68 VEILIGHEIDSINSTALLATIE</b>							subtotaal	<b>3.812</b>	<b>3.991</b>	<b>3.812</b>	<b>3.812</b>	<b>3.812</b>	<b>4.752</b>	<b>3.991</b>	<b>3.812</b>	<b>3.812</b>	<b>3.812</b>	<b>39.414</b>
<b>68 30 Brandblusmiddelen</b>																		
01	Kontralekontraat brandblusapparatuur	2000 - / 1	1 po	3.000	3.630	B	3.630	3.630	3.630	3.630	3.630	3.630	3.630	3.630	3.630	3.630	36.300	
20	Accu's vervangen noodverlichting	2000 - / 5	3 st	49	179	B	.	179	.	.	.	.	179	.	.	.	359	
<b>68 40 Andere veiligheidsinst</b>																		
04 a	Ontruimingsinstallatie aanbrengen	2004 - / 15	1 po	777	940	B	.	.	.	.	.	940	.	.	.	.	940	
10	Onderhoud ontruimingsinstallatie	2004 - / 1	1 st	150	182	B	182	182	182	182	182	182	182	182	182	182	1.815	
<b>80 JAARKONTRAKTEN</b>							subtotaal	<b>8.016</b>	<b>8.016</b>	<b>8.016</b>	<b>8.016</b>	<b>8.016</b>	<b>8.016</b>	<b>8.016</b>	<b>8.016</b>	<b>8.016</b>	<b>8.016</b>	<b>80.162</b>
<b>80 10</b>																		
05	Onderhoud Lift	1996 - / 1	1 po	6.000	7.260	B	7.260	7.260	7.260	7.260	7.260	7.260	7.260	7.260	7.260	7.260	72.600	
05	Onderhoud C.V. ketel	1996 - / 1	1 po	217	262	B	262	262	262	262	262	262	262	262	262	262	2.622	
10	Onderhoud mechanische ventilatie	2010 - / 1	1 po	400	484	B	484	484	484	484	484	484	484	484	484	484	4.840	
20	Kontralekontraat brandblusapparatuur	2000 - / 1	1 ST	8	10	B	10	10	10	10	10	10	10	10	10	10	100	
<b>90 DIVERSEN</b>							subtotaal	<b>2.992</b>	<b>2.992</b>	<b>2.992</b>	<b>2.992</b>	<b>2.992</b>	<b>2.992</b>	<b>2.992</b>	<b>2.992</b>	<b>2.992</b>	<b>2.992</b>	<b>29.918</b>
<b>90 10 Klachten onderhoud</b>																		
01	Gebreken herstellen op klacht	2008 - / 1	1200 m2	2	2.992	B	2.992	2.992	2.992	2.992	2.992	2.992	2.992	2.992	2.992	2.992	29.918	
								<b>75.585</b>	<b>51.877</b>	<b>52.830</b>	<b>104.067</b>	<b>143.411</b>	<b>52.590</b>	<b>46.881</b>	<b>41.681</b>	<b>91.631</b>	<b>95.858</b>	<b>756.411</b>